


History of original corner establishment:



A POST

30" PINE N15E 54 LKS.
4" PINE N47W 72 LKS.

Description of corner evidence found:

38" PINE N15E 35.6' SCRIBING VISIBLE
14" PINE SNAG N47W 47.5' SCRIBING VISIBLE

Description of monument and accessories I established to perpetuate the original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED:

S C	
T5S	
R29E R30E	
S36 S31	
T6S R30E S6	
1978	
PLS 346	

12" FIR N50W 81.1' MARKED: T5S R29E S36 SC BT

ALL BT'S HAVE A RED-PAINTED STRIPE, BEARING TREE TAGS, AND AN ATTENTION SIGN. THE NEW BT HAS A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE. THERE IS A FENCE POST WITHIN 5' OF THE CORNER.



Office of... COUNTY SURVEYOR..... County of... UMATILLA.....
 State of... OREGON..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... 9/11, 1929
W. O. Harris by.....
 (COUNTY OFFICIAL) (DEPUTY)