


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

George S. Pershin under Contract No. 362 dated August 2, 1880.

Set Sand Stone 20 X 12 X 10 from which

Fir, 20" Dia., BRS N42°W., 42 Lks. Dist.  
Pine, 20" Dia., BRS S50°W., 29 Lks. Dist.



Description of corner evidence found:

Found Stone 22 X 11 X 10 marked: 1/4  
Original BTs are now gone.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:  
From which new BTs:

Douglas Fir, 12" Dia., BRS. N13°E., 31.8 Ft. Dist.  
Marked:  $\frac{1}{4}$  S31 SC BT  
Ponderosa Pine, 11" Dia., BRS. N58 3/4°E., 33.2 Ft. Dist.  
Marked:  $\frac{1}{4}$  S31 SC BT  
6' Iron Fence Post with "Attention" sign within 5' of Corner.

SC
T5S R30E
$\frac{1}{4}$ S31
1979
PLS 346


All B.T. have BT tag and painted red stripe; new BTs have brass washer stamped: PLS 346; nailed to lower blaze.

Buried original stone along side iron pipe.

Office of Umatilla County Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 10-17-79 day of October  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 10-17-79  
 Rec'd By WJL  
 No. Q-1171-B



GPO 796-333

2-3