

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 06/16/10

CORNER DESIGNATION: E-19, The North 1/4 Corner of Section 11, Township 5 South, Range 31 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 16x10x8 on Northwest slope in mound of stone for 1/4 section corner.

MONUMENT AND ACCESSORIES FOUND: None. The corner area falls near a gate on the West side of Albee Road. The area has been disturbed by fence and road building.

MONUMENT MARKING DETAIL:

T5S R31E
1 S2
4 S11
2010
PLS 1106

MONUMENT SET: Corner was reestablished by single proportion measure between the Northeast and Northwest Corners of Section 11. At a calculated position, set a 2 3/8" brass cap on 1 1/4"x30" galvanized iron pipe with the cap flush with ground level. Cap is marked as shown in "Monument Marking Detail."

New accessories:

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in railroad fence corner post, bears N 271/2° E, 13.7 feet.

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in power pole, bears S 54° E, 21.5 feet.

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in power pole, bears S 47° W, 30.6 feet.

A 5/8"x24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372", 2" above ground level in fenceline bears N 59° W, 11.9 feet.

Attached bearing object signs beside all brass washers and wired bearing object sign to rebar accessory.

LOCATION AND COMMENTS: Corner is located in level pasture land approximately 15 feet West of a wire gate dividing pastures. Corner is located just NW of Albee Road.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Dean Roy

5S31E19

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-12

10-111-B