

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/26/02

CORNER DESIGNATION: J-17, The Northwest Corner of Section 14, T5S, R31E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 18 x 8 x 6 and post in mound of stone in level plateau for cor. to Sec. 10, 11, 14 & 15.

MONUMENT AND ACCESSORIES FOUND: Found an 18" x 8" x 8" stone with visible notches on two sides laying flat in a small mound of stones, 56 feet South of fence corner with fences North and West. The corner stone and mound of stone is in line with an old downed fence running South at one time. This corner falls on a bare plateau and there are no trees or large stones to mark for accessories.

MONUMENT MARKING DETAIL:

T5S R31E
S10 | S11
S15 | S14
2002
PLS 1106

MONUMENT SET:

At center of stone mound, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 3" above ground and raised a small mound of stone and earth to top of monument, monument marked as shown in "Monument Marking Detail". Buried original stone Southwest of new monument in the stone mound.

New Accessories:

A 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with cap set 1" above ground level, bears N 50° E, 45.3 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with cap set 1" above ground level, bears S 45° E, 53.7 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", with cap set 1" above ground level, bears S 40 1/2° W, 54.0 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground level nailed to a railroad tie H-brace fence corner, bears N 10° W, 57.8 feet.

Attached bearing object signs to all accessories. Attached witness post sign to H-brace at fence corner.

LOCATION AND COMMENTS:

Corner located on bare plateau, 56' South of fence corner with fences North & West.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 541420.61
E = 8604108.14

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\SS31J17



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY
Umatilla County Surveyor
Date 10-02
Rec'd By KR
No. 02-218-B