

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/31/02

CORNER DESIGNATION: L-21, The East Quarter Corner of Section 14, T5S, R31E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 16 x 7 x 6 in mound of stone on level for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: None, the corner area has been farmed and is now a hay field.

MONUMENT MARKING DETAIL:

T5S R31E
1/4
S14|S13
2002
PLS 1106

MONUMENT SET:

Reestablished corner by single proportion measure between the recovered NE Corner of Section 14 and the reestablished SE Corner of Section 14. At position determined by survey, set a 2 1/2" brass cap on a galvanized iron pipe with cap flush with ground with no mound. Corner falls in a hay field. Monument marked as shown in "Monument Marking Detail".

New Accessories:

- A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set 1" above ground level just south of a rock dump, bears N 78° E, 64.8 feet.
 - A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", set in a small water diversion swale bears S 29° E, 66.6 feet.
 - A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", on west side of a large water diversion swale, bears S 80° W, 77.4 feet.
 - A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 36° W, 66.1 feet.
- All accessories have bearing object signs wired to them, set steel fence post 1 foot North of brass cap with witness sign attached.

LOCATION AND COMMENTS: Corner is located in a hay field about 10 feet East of a water diversion ditch or swale.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 538936.31
E = 8609443.77

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
SS31L21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY
Umatilla County Surveyor
Date 10-02
Rec'd By KR
No. 02-218-B