

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/26/02

CORNER DESIGNATION: N-23, the North Quarter Corner of Section 24, T5S, R31E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 18 x 12 x 10 on slight west slope for 1/4 Sec. cor. A Pine 32 in. Di. Brs. N. 17° E. 97 lks. dist. No tree on S. side.

MONUMENT AND ACCESSORIES FOUND: At corner point found an 18" x 12" x 10" set stone marked "1/4" on North face. There is a stump hole N 17°E, 97 links, from this stone (original bearing tree, nothing left of tree except for pitched root crown).

MONUMENT MARKING DETAIL:

T5S R31E
1/4 S13
S24
2002
PLS 1106

MONUMENT SET:

At position of found original stone set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap 3" above ground level, buried original stone on North side of monument in mound of stones. Raised small mound of stones and earth around new monument. Monument marked as shown in "Monument Marking Detail".

New Accessories:

A 6" nail drove into the top of a pitched up 24" diameter ponderosa pine stump cut 24" above ground level, bears N 26 1/2° E, 71.2 feet.

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 55° E, 54.6 feet.

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 30° W, 53.0 feet.

A 5/8" x 24" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 50° W, 64.4 feet.

Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: Corner located on a open North slope.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 536353.48
E = 8612132.21

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
V5S31N23

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renewals 6-30-04

RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KK

No. 02-218-B