


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index No. N-3

History of original corner establishment:

Surveyed by George S. Pershin under Contract No. 373 dated September 17, 1880. The original notes state that at the corner a basalt stone 18" x 12" x 5" was set on a south slope for the corner from which: A 24" pine bears N82°W 112 LKS (73.9 ft) A 5" pine bears S28°W 85LKS (56.1ft)



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

Found basalt stone 18" x 15" x 5" with no markings. Found a 24" stump bears N84°W 73.9 ft. from center, no scribing found.. A down and rotten pine bears S29°W 56.1 ft from center marked 1/4 S BT.

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 6 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post West of corner and attached sign 54-4. Established 2 new BT's: A 10" bullpine bears S31 1/2°W 19.6 ft scribed 1/4 S 19BT . A 9 1/2" bullpine bears N74°W 23.8 ft. scribed 1/4 S 18BT New BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it. BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze .

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts. See map of survey.


This corner set July 29, 1979

Witnesses: Greg Flowers, L.S.I.T. Brent Reynolds

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106



Office of County Surveyor County of Umatilla State of Oregon, I hereby certify that the within instrument was filed in this office for record on the day of by (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Form R6-7100-57 (9/71)

Date Sept 4, 1979 Rec'd By M. Hughes No. 2-1164-B