

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/04/02

CORNER DESIGNATION: P-21, The East 1/4 Corner of Section 23, T5S, R31E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated Sept. 17, 1880. Notes state: Set basalt stone, 18 x 10 x 4, on N. slope for 1/4 Sec. Cor. A pine, 32 ins. diam., brs. N. 14° E., 118 lks. dist. A pine, 40 ins. diam., brs. S. 50° W., 129 lks. dist.

MONUMENT AND ACCESSORIES FOUND:

Found both original bearing trees. Bearing tree N 14°E, 118 links is cut approximately 15" above ground level with no visible scribing, diameter approximately 32". Bearing tree at S 50° W, 129 links is cut approximately 30" above ground level with scribing "BT" visible, scribing measures 20" out from centerline of stump (40" diameter stump). Found the original stone marked "1/4" in a rock jack 8' South of corner position.

MONUMENT MARKING DETAIL:

T5S R31E
1/4
S23 | S24
2002
PLS 1106

MONUMENT SET:

Reestablished corner position by distance-distance from original bearing trees, measuring from face of blaze. At reestablished corner position, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe with cap 4" above ground level in a North-South fence, marked as shown in "Monument Marking Detail". Buried original stone on West side of brass cap monument and raised a small mound of stone and earth around monument.

New Accessories:

A 23" ponderosa pine scribed "1/4 S24 BT", bears N 52 1/2° E, 98.2 feet.
A 18" ponderosa pine scribed "1/4 S24 BT", bears S 70 1/2° E, 82.1 feet.
A 16" ponderosa pine scribed "1/4 S23 BT", bears S 70° W, 75.7 feet.
A 12" ponderosa pine scribed "1/4 S23 BT", bears N 43° W, 65.4 feet.
Attached bearing object signs to new bearing trees and to both original bearing tree stumps.

LOCATION AND COMMENTS: Corner falls in a North-South Fence line.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 533664.76
E = 8609539.80

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
5S31P21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

RECEIVED BY

Umatilla County Surveyor

Date 10-02

Rec'd By KK

No. 02-218-6