

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/28/02

CORNER DESIGNATION: R-17, The Northeast Corner of Section 27, T5S, R31E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George S. Pershin, under Contract No. 373, dated September 17, 1880. Notes state: Set basalt stone 18 x 10 x 8, on slight North slope, in mound of stone for cor. to Secs. 22, 23, 26 & 27. A pine 42 ins. diam., brs. N 13° E., 392 lks. dist. A pine 20 ins. diam., brs. S 05° W., 234 lks. dist. No other trees.

MONUMENT AND ACCESSORIES FOUND: Found original bearing tree with opened blaze and scribing visible S 05° W 234 lks., from a small mound of stone. Found the original marked stone with 2 notches on two edges, laying flat about 8 feet North of mound of stone. There is no evidence of the other bearing tree N 13° E., 392 lks. dist. The mound of stone is accepted for the corner as it fits the original bearing and distance from the original found bearing tree.

MONUMENT MARKING DETAIL:

T5S R31E  
S22 | S23  
S27 | S26  
2002  
PLS 1106

MONUMENT SET:

A center of the stone mound, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe 16" in the ground and surrounded with a mound of stone. Monument marked as shown in "Monument Marking Detail". Buried original stone on North side of brass cap in mound of stone.

New Accessories:

"XBO" chiseled into the top of a 30" x 22" x 10" above ground stone in place bears N 39° E, 52.8 feet.

"XBO" chiseled into the top of a 30" x 27" x 11" above ground stone in place bears S 42° E, 69.6 feet.

The original SW bearing tree, a 40" diam. ponderosa pine with opened blaze and scribing visible bears S 05° W, 154.5 feet to blaze face.

A 3/4" brass washer stamped "PLS 1106" 1.0 feet above ground nailed to a rock jack fence post bears S 10° W, 70.1 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 feet above ground nailed to a rock jack fence post bears N 03 1/2 ° W, 51.4 feet.

Attached bearing object signs to all accessories except "XBO" rocks. Measured to the "X" on "XBO" accessories. Attached witness sign to rock jack Northwesterly 15 feet from corner.

LOCATION AND COMMENTS:

Corner falls in a "minefield" of surface stones 6 feet East of a fence running North-South.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
\\SS31R17

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-04*

RECEIVED BY  
Umatilla County Surveyor  
Date 10-02  
Rec'd By KK  
No. 02-218-B