


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

7

History of original corner establishment:
None

Index No. S-4



No record of subsequent remonumentation found in County Records .
Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 6 inches in the ground and surrounded with a mound of stones to the cap .
Set steel fence posts South and West on line from corner and attached signs 54-2 and 54-9.
Established 2 new BT's: A 10 1/2" bull pine bears N28 1/2° E 223.5 ft. scribed NE 1/16 S 30 BT.
A 13 1/2" bull pine bears N 48 1/2° E 228.3 ft. scribed NE 1/16 S 30 BT.
BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.
Location marker on fence post where fence crosses road. Corner 1500' feet + West of location poster.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.
See map of survey


This corner set August 21, 1979

Witnesses: Greg Flowers L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon , I hereby certify that the within instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date Sept 4, 1979
Rec'd By M. Hughes
No. Q-1164-B