

USDA-FOREST SERVICE

Index  
File No. T-2

T 5S R. 31E

Merid. Willamette

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or Survey No. Sec. 30 Cor. No. C.W. 1/16

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner located in the bottom of a small canyon on the east side of a dry stream bed.

Signature William R. Wells Title PLS 1106

Division \_\_\_\_\_ Headquarters \_\_\_\_\_

Date 8/21/79

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2" x 30" galvanized iron pipe with a brass cap 15 inches in ground with a mound of stone to the cap, marked:

Set steel fence post on line North of corner and attached signs 54-2 and 54-9.

TSS R31E

C  $\frac{W/16}{\bullet}$  C

S30

1979

PLS 1106

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set 2 New BT's:

BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush. Attached signs 54-3 and 54-4 and painted red ring around BT's.

10

Work Done By William R. Wells Title PLS Date 8/21/79 State Registration No. 1106  
or Agency  
Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor's Office Date

11

REMARKS

Note: This corner was established in error in 7/79 and bearing trees established. When the corner was established in its true position, scribing and signs were removed from the BT's referencing the erroneous position. From the correct corner position:

A 8 1/2" red fir bears N 16 1/2° E 50.5 ft with open blaze

A 8" bullpine bears S 35 1/2° E 42.3 ft with open blaze

12

Index File No. T. R. M. Tract or Surv. No. Sec. 30 Cor. C, W, 1/16  
U.S. G.P.O. 1977-725-576/586  
T-2 5S 31E Willamette