


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

V-2

Index No. V-2

History of original corner establishment:

None



No record of subsequent remonumentation found in County Records .  
Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 22 inches in the ground and surrounded with a mound of stones to the cap .  
Set steel fence posts on property line South and East of corner and attached signs 54-2 and 54-9.  
Established 2 new BT's:  
A 11" bullpine bears N30°W 2.5 ft. scribed W 1/16 S 30 BT.  
A 10" bullpine bears S57°W 55.3 ft. scribed W 1/16 S31 BT.  
BT's have lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.  
BT's have 54-3 and 54-4 signs attached and a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.  
See map of survey


This corner set July 29, 1979

Witnesses: Greg Flowers, L.S.I.T.  
Brent Reynolds

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106



Office of County Surveyor County of Umatilla  
State of Oregon , I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

**RECEIVED BY**

**Umatilla County Surveyor**

Date Sept 4, 1979

Rec'd By M. Hughes

No. Q-1164-B