



WAYNE HARRIS Co., INC. E-21

P.O. Box 566 S.E. 17th & Court Pl. Pendleton, OR. 97801

(503) 276-7642

Notes for Resetting:

The Northwest corner of Section 12, Township 5 South, Range 32 East, W.M.

I found a stump of a Ponderosa pine that had a BT carved in it. Assuming this stump to be the original 28" pine bearing North 43° East links, I back tracked South 42° West 96 links. This point was in bank of small stream in a meadow or swale composed of alluvial soil.

At this point I started to dig. The soil was very friable and contained no rocks. A few inches under the surface I found a stone with several stones nearby. This stone fit the description of the stone placed there by the original surveyor; this stone was sitting in a position in which surveyors customarily place them. There were no other stones in the vicinity of this group.

As a further check I measured the called bearings and distances of the original survey. In all cases I found rotted stumps fitting the calls. However I was unable to find markings in the deteriorated wood.

A further check showed old fence lines converging in this direction,

I therefore accepted this stone as being the original corner and placed a 1½" galvanized iron pipe with a brass cap marked:



From this stone witness trees were marked as follows:

A 14" Ponderosa Pine bears	
N 17° W - 83.0 feet	S ₁ 2
	BT
A 14" Ponderosa Pine bears	
N 62° E - 107.4 feet	S ₁ 1
	BT
A 26" Ponderosa Pine bears	
S 20° W - 116.0 feet	S ₁ 11
	BT

Wayne O. Harris
Wayne O. Harris
RLS #346

RECEIVED BY

Umatilla County Surveyor

Date 4-81

Rec'd By BLS

No. S-28-M