


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-25

History of original corner establishment:

George S. Pershin under Contract no. 390 dated May 12 1882, set a basalt stone 20 x 10 x 5 in a mound of stone on North slope West of a shallow ravine from which:
 A Pine 10" dia. bears N. 70°E 56 LKS (37.0 ft)
 A Pine 10" dia. bears S 18°E 60 LKS (39.6 ft.)



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

A mound of stone on North slope West of shallow draw.
 Stump of a pine 30" dia. snag, bears N74½°E, 37.4 ft. to center scribed T5S R33E S5.
 A 33" Pine bears S 14½°E 40.0 ft to center, Healed blaze has been chopped out and appears to have been chopped too deep.

Description of monument and accessories I established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 12 inches in the ground and surrounded with a mound of stones to the cap.
 Set a steel fence post North of corner and attached sign 54-4.

Set 4 new BT's:

A 13" bullpine bears N4½°W 57.3 ft., marked T5S R32E S12 BT
 A 16½" bullpine bears N34°E 51.0 ft., marked T5S R33E S7 BT
 A 13½" bullpine bears S63°E 150.0 ft., marked T5S R33E S18 BT
 A 10½" bullpine bears S37°W 42.1 ft marked T5S R32E S13 BT
 New BT's have lower blaze scribed BT, with a brass washer stamped PLS 1106 nailed to it.
 BT's have 54-3 & 54-4 signs attached & a 6" red band painted around them above blaze.

Used steel tape and magnetic compass with 19½° east declination . Measured to center of Bts.
 See map of survey.


This corner set July 25, 1979

Witnesses: Greg Flowers, L.S.I.T.
 Brent Reynolds

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106



Office of County Surveyor County of Umatilla
 State of Oregon , I hereby certify that the within instrument was filed in this office
 for record on the day of ..
 by
 (COUNTY OFFICIAL) (DEPUTY)

J-25

RECEIVED BY
Umatilla County Surveyor
 Date August 20, 1979
 Rec'd By M. Hughes
 No. Q-1134-B corresponding
 drawing