


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by the Bureau of Land Management during surveys performed between 1967 and 1980. Point for the center W 1/16 sec. cor. of Section 35. Set an iron post, 28 ins. long, 2 1/2 ins. in diam., 20 ins. in the ground, in a mound of stones, 3 ft. base to top, with brass cap, marked:



from which:
A Fir, 12 ins. diam. bears S 46°E
38 lks. dist. mkd. CW 1/16 S 35 BT.
No other suitable trees available within limits.

W 1/16
C ——— C
S 35
1968

Description of corner evidence found:

Found a 2 1/2" dia. iron pipe, set as described in the official BLM record, with brass cap attached, marked: U.S. Dept. of Interior, Bureau of Land Management

from which:
A 14" Douglas Fir, alive and well-healed bears S 46°E 25.1 feet.

W 1/16
C ——— C
S 35
1968

Description of monument and accessories established to perpetuate the original location of this corner:

We mark a new BT:

An 8" Douglas Fir, scribed "CW 1/16 S 35BT" on a double blaze bears S 40°W 66.1 feet. Attached brass washer marked "LS 1099" to lower blaze.

Corner of fences S and W bears 70' South and 80' West.

Magnetic Compass (Declination 20° East)
Steel Tape

August 15, 1984

Witnesses:

Gary Langlitz, LS 1099
Ray Crapo
Greg Orton



Office of Surveyors County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 15 day of October 1984
David Krummen by Betty Cochran
(COUNTY OFFICIAL) (DEPUTY)