


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by George S. Pershin under General Land Office Contract No. 410. Surveyor General Records state:
 Set basalt stone 16 X 12 X 5 ins. for cor. to secs 34, 35, 2, 3 from which:
 A Pine 7 ins. dia. brs. S 64° E, 44 lks. dist.
 A Pine 14 in. dia. brs. S 3° W, 56 lks. dist.
 No other trees near, raised mound of stone along side.



No record of subsequent remonumentation was found in county records.


Description of corner evidence found:

Found 20" Pine stump with BT visible; remains of the SW BT. Stone was not found. No evidence of SE BT.

(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At record bearing and distance from SW BT I set 2 1/2" X 30" iron pipe with brass cap marked as shown 20" in ground, from which:
 A 16" Lodgepole Pine bears N 67° E, 83.6 ft. marked T4S R33E S35 BT.
 A 20" Lodgepole Pine bears S 75° E, 22.0 ft. marked T5S R33E S2 BT.
 A 14" Lodgepole Pine bears S 12° W, 202.2 ft. marked T5S R33E S3 BT.
 A 8" Lodgepole Pine bears N 66° W, 288.2 ft. marked T4S R33E S34 BT.
 Raised mound of stone 5 ft. base to top of cap.
 Set steel fence post 5+ ft. West and South.



**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Duane I. Griffith
OREGON
 JULY 10, 1904
DUANE I. GRIFFITH
 644

Brass Washer nailed to BT blazes. Used steel tape and magnetic compass with 19°30' East declination. Measured to center of all BTs.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the day of.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

2-17