


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-19

History of original corner establishment:

No record of previous monumentation.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{2}$ "x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

T5S R33E
C $\frac{1}{2}$ S2
PLS 1832
1984

No trees within a reasonable distance of the corner.

From the corner:

A 5/8" iron rod (Rebar), 30" long, driven in the ground, with a 1 $\frac{1}{2}$ " yellow plastic cap marked: PLS 1832 bears S31 $\frac{1}{2}$ °E, 14.22 ft.

A 5/8" iron rod (Rebar), 30" long, driven in the ground, with a 1 7/8" alum. cap marked: PLS 1832

bears N58 $\frac{1}{2}$ °E, 11.35 ft. RM

There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to iron rods using steel tape and staff compass. Magnetic declination set at 18 $\frac{1}{2}$ °E.

September 13, 1984.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of... Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the... 10... day of... October 1984
David H. Krumbach by
(COUNTY OFFICIAL) (DEPUTY)

C-19

84-128-R