


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-21

History of original corner establishment:

Corner established under G.L.O. Contract No. 430, in 1882 by George S. Pershin. Surveyor General's records state: Set basalt stone 16x7x6 in. 11 ins. in ground on level at small grove of Pine Trees for 1/4 Sec. Cor. marked 1/4 on W. face from which:
 A Pine 8 ins. dia. brs. S58°E, 23 lks. dist marked 1/4 S BT.
 a Pine 7 ins. dia. brs. N51°W, 33 lks. dist marked 1/4 S BT.




Description of corner evidence found:

Found original stone 16"x7"x6" - 10" in ground with visible " $\frac{1}{4}$ " on west face.
 Could find no evidence of original Bearing Trees.

Description of monument and accessories I established to perpetuate the original location of this corner:

In place of original stone set 2 1/2"x30" galvanized pipe with brass cap stamped:
 Set pipe 24" in ground with mound of stone to cap and original stone buried alongside.



New Bearing Trees:

A Lodge Pole Pine 7" in dia. bears S76°W, 45.5 ft., scribed 1/4 S2 BT.
 A Lodge Pole Pine 5" dia. bears S85°E, 149.7 ft., scribed 1/4 S1 BT.

Attached 54-3 & 54-4 signs to both BTs. Attached brass washer stamped LS1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs Red.
 Attached 54-2 & 54-4 signs to metal post 3 ft. west of corner.

I hereby certify the above corner monument was re-established as herein described on May 30, 1980.

Witnesses: R. Orgon
 G. Lester
 L. Huntsman



Office of..... County Surveyor..... County of..... Umatilla
 Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... *December*..... 19.....⁸⁰
David R. Huntsman..... by..... *Patty Shatto*
 (COUNTY OFFICIAL)..... (DEPUTY)