


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-23

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:


Set pipe 22" in ground with mound of stone to cap.

Bearing Trees:

A Lodgepole Pine 7" dia., bears N25°E, 71.4 ft., scribed C 1/2 S1 BT.

A Ponderosa Pine 10" dia., bears S82°W, 67.6 ft., scribed C 1/2 S1 BT.

Attached 54-3 and 54-4 signs to both BTs. Attached brass washer stamped LS 1294 to foot blaze of both BTs. Painted blazes and 6" band around both BTs RED. Attached 54-2 and 54-4 signs to metal post 6 ft. East of corner. Attached 54-2 and 54-9 signs to metal post 6 ft. North of corner.



I hereby certify the above corner monument was established as herein described on June 13, 1980.

Witnesses: R. Orton  
G. Orton  
D. Allen

Office of..... County Surveyor..... County of..... Umatilla  
Oregon  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of..... 19 80  
..... by.....  
(COUNTY OFFICIAL) (DEPUTY)