


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

D-20

**History of original corner establishment:**

No record of previous monumentation.



**Description of corner evidence found:**

None.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set a 2 1/2"x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

SE 1/16 S2  
PLS 1832  
1984

Built a stone mound around the monument.

From the corner:

A D. Fir, 6" dia., S69 3/4°W, 18.0 ft. marked: SE 1/16 S2 BT  
A P. Pine, 6" dia., S90°S, 16.4 ft. marked: SE 1/16 S2 BT

BTs have blaze and a 6" stripe painted red, a BT tag, a "Land Survey Monument" sign and an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 21°E.

September 13, 1984.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Fayette S. Munro*

OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832

Office of Surveyor..... County of Umatilla.....  
State of Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the 10 day of October..... 1984  
David H. Keumbain..... by [Signature].....  
(COUNTY OFFICIAL) (DEPUTY)

84429R