

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


8-19

History of original corner establishment:

This corner was originally established by George S. Pershin under G.L.O. contract no. 430 dated March 23, 1882. He set a basalt stone 12"x10"x6" marked $\frac{1}{4}$ on the north side.

From which:

- A Fir, 12" dia., N31⁰E, 26 lks.
- A Pine, 20" dia., S28⁰W, 13 lks.



Description of corner evidence found:

Found a stone 12"x10"x6" with no marks evident, firmly set.

From which:

- A D. Fir snag, 16" dia., N33⁰E, 16.3 ft. with scribing visible.
- A P. Pine, dead and down, 23" dia., with scribing visible, the the root hole of which bears S36⁰W, 17.2 ft.

Description of monument and accessories | established to perpetuate the original location of this corner:

In place of the original stone set a 2 $\frac{1}{2}$ "x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

T5S R33E

Buried the original stone alongside of and built a stone mound around the monument.

$\frac{1}{4}$ $\frac{S2}{S11}$

Mark new BTs:

PLS 1832
1984

- A D. Fir, 11" dia., N11⁰W, 18.8 ft. marked: $\frac{1}{4}$ S2 BT
- A D. Fir, 11" dia., S42 $\frac{1}{4}$ ⁰W, 38.9 ft. marked: $\frac{1}{4}$ S11 BT

BTs have blaze and a 6" stripe painted red, a BT tag and an "Attention" sign. New BTs have, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 16 $\frac{1}{2}$ ⁰E.

Magnetic

September 16, 1984

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of Surveyor..... County of Umatilla.....
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 10 day of October..... 1984
David H. Keumbein by
 (COUNTY OFFICIAL) (DEPUTY)

84-126-R