


History of original corner establishment:

Corner established by George S. Pershin under Contract No. 430 dated 1882. The original notes state at the corner a post 4' long 4 in. square and a marked stone were set in a mound of stone, on level ground. The marked stone was basalt, 16" x 8" x 5" in size marked with 4 notches on South and 4 notches on the East. No BT's were established.



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

None . Corner re-established by double proportion measurement.

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 10 inches in the ground and surrounded with a mound of stones to the cap. Set a steel fence post East of corner and attached signs 54-2 & 54-4.

Establish 4 new BT's:

A 9 1/2" bullpine bears N63°W 73.2 ft. . marked T5S R33E S8 BT.

A 14 1/2" bullpine bears N43°E 132.5 ft. . marked T5S R33E S9 BT.

A 11 1/2" bullpine bears S54°E 113.8 ft. marked T5S R33E S16 BT.

A 11 1/2" bullpine bears S39 1/2°W 86.8 ft. T5SR33E S17 BT.

New BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

New BT's have 54-3 & 54-4 signs attached and a 6" Red band painted around them above blaze.

Location poster located on south side of road on open ridge 350'± North of corner.

Used steel tape and magnetic compass with 19 1/2° east declination. Measured to center of Bts.

See map of survey


This corner set July 26, 1979

Witnesses: Greg Flowers L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla

State of Oregon I hereby certify that the within instrument was filed in this office

for record on the day of

..... by (COUNTY OFFICIAL) (DEPUTY)

J-9

RECEIVED BY
Umatilla County Surveyor
Date August 20, 1979
Rec'd By *M. Hughes*
No. *Q-1134-B* corresponding drawing