

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


N-03
140400
T. 5 S., R. 33 E.
1/4 corner of sections 18 & 19

History of original corner establishment:

1882, George S. Pershin, U.S. Deputy Surveyor, while subdividing the township under G.L.O. Contract No. 430 established the corner as follows:

Set Basalt Stone 18 X 8 X 7 ins 12 ins in ground on level in grove for 1/4 Sec. cor. marked 1/4 on North face
A Pine 18 in. dia. brs. N. 22° E. 52 lks dist marked 1/4 S.B.T.
A Pine 22 in. dia. brs. S. 42° W. 106 lks dist marked 1/4 S.B.T.

1984, David H. Krumbein, LS 933, (CS# 84-161-R) Found the S.W. Bearing Tree which is now a 24" dia. weathered stump with fragmentary scribes visible. From the corner location as established from the S.W. Bearing tree. An 18" badly weathered stump matches the GLO Bearing and distance. The corner was set from these stumps.




Set a 2 1/2" dia. Brass Cap on a 2 1/2" X 30" galvanized pipe set 16" in the ground and mound of stones around Brass Cap. From which scribed the Bearing Trees.

A 7" dia. Ponderosa Pine bears N 25° W, 101.00 feet scribed 1/4 S18 BT
A 7" dia. Ponderosa Pine bears S 46° E, 32.00 feet scribed 1/4 S19 BT

Description of corner evidence found:

Found a 2 1/2" diameter iron pipe, with 2 1/2" diameter brass cap, projecting 8" out of the ground, surrounded by a ring of stones, marked as shown, from which:



- 20" stump bears N 13° E, 35.0 feet, with no marks.
- 14" Ponderosa Pine bears S 42 1/2° E, 32.0 feet, with healed blaze.
- 21" burnt stump bears S 51° W, 77.2 feet, with fragmentary scribing visible.
- 15" Ponderosa Pine bears N 22 1/4° W, 101.0 feet, with healed blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

New References:

- 13" Ponderosa Pine bears S 20 1/4° E, 94.1 feet, scribed "1/4 S19" "BT"
- 12" Ponderosa Pine bears S 13 1/4° W, 62.9 feet, scribed "1/4 S19" "BT"

The new bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

DATUM: NAD83(1991) Oregon High Accuracy Reference Network
STATE PLANE COORDINATES: Oregon North Zone in International Feet
No. Latitude Longitude Northing(Y) Easting(X)
140400 45°07'37.80070" N. 118°46'05.36670" W. 537246.388' 8649026.099'

Work Performed By: David A. Schlaich (RLS 2308)
Witnessed By: Matthew Duffy
Equipment: Warren-Knight Surveyor's Compass
Magnetic Declination: 19 1/2° East
Date: September 23, 2002

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2004

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....
..... by.....
(COUNTY OFFICIAL) (DEPUTY)