


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-3

History of original corner establishment:

Corner was established by George S. Pershin in 1882 under contract # 430 Set was a Basalt Stone 18"x 8" x 7", 12" in the ground marked 1/4" on North face A 18" Pine bears N 22° E, 52 links scribed 1/4 S BT A 22" Pine bears S 42° W, 106 links scribed 1/4 S BT




Description of corner evidence found:

Found the S.W. Bearing Tree which is now a 24" dia. weathered stump with fragmentary scribing visible. From the corner location as established from the S.W. Bearing tree. An 18" badly weathered stump matches the GLO Bearing and distance. The corner was set from these stumps.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" dia. Brass Cap on a 2 1/2" x 30" galvanized pipe set 16" in the ground and mound of stones around the Brass Cap which is stamped as shown: From which I scribed the Bearing Trees. A 7" dia. Ponderosa Pine bears N 25° W, 101.00 feet scribed 1/4 S18 BT A 7" dia. Ponderosa Pine bears S 46° E, 32.00 feet scribed 1/4 S 19 BT Bearing trees have: A Brass Washer stamped PLS 933 nailed to the BT scribe, a painted band around the tree and on the face of the scribe, signs # 54-3 & 54-4 Bearing trees were measured horizontally with a steel tape to the center of the tree and a magnetic compass with a 19° East variation. Also set a steel fence post with sign # 54-4 by Brass Cap. July 5, 1984 Witness: R. Panches S. Carlson



Office of Surveyors County of Umatilla State of Oregon I hereby certify that the within instrument was filed in this office for record on the 21st day of November 1984 by Betty Cochran (DEPUTY)