


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George Pershin under General Land Office Contract No, 430. Surveyor General Records states:

Set basalt stone 16" x 10" x 8" for  $\frac{1}{4}$  corner from which:

- A pine 20 in. dia. bears N 86 W, 33 lks. dist.
- A pine 18 in. dia. bears S 85 W, 24 lks. dist.



Description of corner evidence found:

Found 26" Pipe, NW BT, scribes visible.

No evidence of other BT found.

Description of monument and accessories established to perpetuate the original location of this corner

At record bearing and distance from the NW BT I set  $2\frac{1}{2}$ " x 30" iron pipe with brass cap marked as shown 26" in ground from which:


Original BT:

A 26" P. Pine bears N 86 W, 21.8 ft. scribes visible.

New BT's:

- A 10" P. Pine bears N 89 W, 31.5 ft. marked T5S R33E  $\frac{1}{4}$ S17 BT.
- A 10" P. Pine bears S 04 E, 29.6 ft. marked T5S R33E  $\frac{1}{4}$ S20 BT.

Set steel fence post 5' East.  
Raise mound of stone.



Brass washer nailed to BT blazes.  
Used steel tape and magnetic compass with 19° 30' East declination.  
Measured to center of BTs.

Office of ..... County of .....

State of ....., I hereby certify that the within instrument was filed in this office for record on the ..... day of .....

..... by ..... (DEPUTY)

(COUNTY OFFICIAL)

*Noted 90 set*