


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-11

History of original corner establishment:

None




Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner: By Proportionate Method

Set a 2½" dia. Brass Cap on a 2½" x 30" galvanized pipe 12" in the ground and a mound of stones around the Brass Cap which is stamped as shown:  
 From which I scribed the Bearing Trees.  
 A 7" dia. Lodge Pole Pine bears N 59° W, 13.8 feet scribed C¼ S21 BT  
 A 7" dia. Lodge Pole Pine bears N 83° E, 16.7 feet scribed C¼ S21 BT  
 Bearing trees have: A Brass Washer stamped PLS 933 nailed to the BT scribe, a painted band around the tree and on the face of the scribe, signs # 54-3 & 54-4  
 Bearing trees were measured horizontally with a steel tape to the center of the tree and a magnetic compass with a 19° East variation.  
 Also set a steel fence post with sign # 54-4 by Brass Cap.  
 July 5, 1984  
 Witness: R. Panches  
 S. Carlson



REGISTERED PROFESSIONAL LAND SURVEYOR

David H. Krumbein  
OREGON JULY 17, 1970 DAVID H. KRUMBEIN 933

Office of Surveyor County of Umatilla  
 State of Oregon I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of November, 1984  
 by Betty Cochran  
 (COUNTY OFFICIAL) (DEPUTY)