


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

P-05  
200340  
T. 5 S., R. 33 E.  
1/4 corner of sections 19 & 20

History of original corner establishment:

1882, George S. Pershin, U.S. Deputy Surveyor, while subdividing the township under G.L.O. Contract No. 430 established the corner as follows:  
Set a basalt Stone 17 X 10 X 5 ins 12 ins in ground for 1/4 sec. cor. marked 1/4 S on West Side raised mound of stone alongside



1984, David H. Krumbein, LS 933, (CS# 84-159-R) did not find any evidence. By Proportionate Method Set a 2 1/2" dia. Brass Cap on a 2 1/2" X 30" galvanized pipe 15" in the ground and a mound of stones around Brass Cap. From which scribed the Bearing Trees.  
A 12" dia. Ponderosa Pine bears N 48° E, 15.9 feet scribed 1/4 S20 BT  
A 8" dia. Ponderosa Pine bears N 39° W, 25.1 feet scribed 1/4 S19 BT

1995, The Bureau of Land Management while computing geodetic coordinate positions for Public Land Survey Corners discover that Krumbein used an incorrect record measurement when he proportioned the corner.

Description of corner evidence found:

Found Krumbein's erroneously established corner as described in the county records. No evidence of the original stone was found.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set at proportionate distance a 2 1/2" diameter by 30" long aluminum pipe, with 3 1/4" diameter aluminum cap, 18" in the ground, with white SURV-KAP magnetic reference set in the bottom of the hole, surrounded by a rock mound 2 feet in diameter by 1 foot high, in a North-South fenceline, marked as shown, from which:



17" Ponderosa Pine bears S 87 3/4° E, 26.6 feet, scribed 1/4 S20 "BT".  
12" Ponderosa Pine bears S 41 1/2° E, 58.3 feet, scribed 1/4 S20 "BT".  
19" Ponderosa Pine bears S 10 3/4° W, 47.9 feet, scribed 1/4 S19 "BT".  
11" Ponderosa Pine bears N 62 1/4° W, 40.1 feet, with scribing visible on partially healed blaze.  
The 1/4 corner of sections 19 and 20, erroneously established by Krumbein in 1984, bears S 86°37'37" W, 19.43 feet. Monumented with 2 1/2" diameter iron pipe with a 2 1/2" diameter brass cap firmly set, in a mound of stones, with brass cap marked and witnessed as described in the county records.

As per the direction of David H. Krumbein, Umatilla County Surveyor, I remove the 1984 monument and destroy the marks on the 1984 NE BT.

The new bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

DATUM: NAD83(1991) Oregon High Accuracy Reference Network  
STATE PLANE COORDINATES: Oregon North Zone in International Feet  
No.                      Latitude                      Longitude                      Northing(Y)                      Easting(X)  
200340                      45°07'12.14254" N.                      118°45'28.53882" W.                      534705.326'                      8651721.703'

Work Performed By: David A. Schlaich (RLS 2308)  
Witnessed By: Matthew Duffy  
Equipment: Topcon GPT-6005C Total Station  
Magnetic Declination: 19 1/2' East  
Date: September 26, 2002

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*David A. Schlaich*

OREGON  
JULY 16, 1987  
**DAVID A. SCHLAICH**  
2308

RENEWAL DATE: 06/30/2004

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 20.....  
..... by.....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

SEE MAP OF SURVEY NO. 03-019-B