


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

R-5


**History of original corner establishment:**

Corner was established by George S. Pershin in 1882 under Contract # 430  
 Set was a basalt stone 18 x 8 x 6 inches with 5 notches on East and 2 notches on South edges  
 In 1977 the BLM remonumented this corner and found the original stone loosely set 1" in the ground and; a root hole bears N 69° E, 239 lks with a down and decayed pine alongside, size indeterminate, and a pine, 38" dia., bears S 64° E, 279 lks with fragmentary scribe marks.  
 They scribed a new bearing tree, a Lodgepole pine, 18" dia., bears N 59½° E, 308 lks, marked T 5 S, R 33 E, S 20 BT



**Description of corner evidence found:**

Found a BLM Brass Cap stamped as shown:  
 A 12" Ponderosa Pine bears N 59° E, 262 feet scribed  
 T 5 S R 33 E S 20 BT  
 A 40" Ponderosa Pine bears S 64° E, 279 links with fragmentary scribing visible



**Description of monument and accessories established to perpetuate the original location of this corner:**

Set a 5/8" x 30" iron rebar with an aluminum cap stamped PLS 933 N 45° W, 20.00 feet  
 Set a 5/8" x 30" iron rebar with aluminum cap stamped PLS 933 S 45° W, 20.00 feet  
 Work was done with a staff compass set at 20° East variation  
 Distance was measured with a steel chain  
 August 6, 1984  
 Witness: R. Panches  
           S. Carlson



Office of Surveyor ..... County of Umatilla  
 State of Oregon ..... I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of November, 1984  
 ..... by Betty Cochran  
 (COUNTY OFFICIAL) (DEPUTY)