


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-5

**History of original corner establishment:**

George S. Pershin under G.L.O. Contract No. 430, dated Mar. 23, 1882, set a basalt stone 16"x 10"x 7", 11" in ground, marked  $\frac{1}{4}$  on N. face. From corner: Tamarack 26" dia., N58°E, 14 lks. Fir, 20" dia., N70°W, 33 lks.



Craig L. Wanless, Cadastral Surveyor, under special instructions, Group No. 350, found a basalt stone 16"x 10"x 7" marked  $\frac{1}{4}$ . He set a 2 $\frac{1}{2}$ "x 28" iron post with brass cap marked:

T5S R33E

From corner:

$\frac{1}{4}$

Larch, 40" dia., N70°E, 14 lks.; scribing visible. (orig. BT) Root hole, N70°W, 33 lks.; down and decayed fir alongside; scribing visible.. (orig. BT)

S301S29  
1977

Grand Fir, 10" dia., N51°W, 19 lks. (new BT)

**Description of corner evidence found:**

I found a 2 $\frac{1}{2}$ " iron pipe with a 3 $\frac{1}{4}$ " brass cap (BLM) marked as above. Monument is in mound of stone. From the corner: Douglas Fir, 13" dia., N51°W, 12.5 ft.; scribing visible.. W. Larch, 37" dia., N70°E, 9.2 ft.; " " ; tree is dying.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

I marked new BTs:

Douglas Fir, 12" dia., N21°E, 10.5 ft.; marked:  $\frac{1}{4}$  S29 BT  
Ponderosa Pine, 12" dia., S72 $\frac{1}{4}$ °E, 9.3 ft.; marked:  $\frac{1}{4}$  S29 BT  
Ponderosa Pine, 8" dia., S21 $\frac{1}{2}$ °E, 55.8 ft.; marked:  $\frac{1}{4}$  S29 BT

BTs have blaze and a 6" band painted red, BT tags and "Land Survey Monument" signs. New BTs have, additionally, alum. "PLS 1832" washers nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 19°E..

June 9, 1991

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Fayette S. Munro*

OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 12-91

Rec'd By JK

No. 91-97-R

GPO-798-276