


History of original corner establishment:

This corner was originally established by George S. Pershin under Contract No. 362 dated August 2, 1880. The original notes state that at the corner a 18x12x10" basalt stone was set for the corner from which:

- A 10" pine bears N34°W 11 lk (7.3 ft)
- A 5" Pine bears N52°E 35 lk (23.1 ft)

No record of subsequent remonumentation found in County Records.



Description of corner evidence found:

Found 18"x12"x10" basalt stone set firmly in the ground with 3 distinct notches in the east edge. An old uprooted stump, scribed BT was found lying SW of stone about 6 feet. There is a depression (stump hole) N34°W 7.3 feet from stone. The BT stump found has apparently been pushed down the hill during fence building. Placed BT stump in depression. The northeast corner of section 3 (a closing corner) bears East 29.5 feet. An East-West fence bears North 3.5 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 26 inches in the ground and surrounded with a mound of stones to the cap. Set steel fence post West of corner with signs 54-2 and 54-4 attached. Buried stone below ground next to new monument.

Established 2 new BT's:

A 11" Ponderosa Pine bears N11½°E 24.6 ft scribed T5S R33E S34 SC BT

A 25" Ponderosa Pine bears N85½°E 92.6 feet scribed T5S R33E S34 SC BT

New BT's have a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush.

Attached signs 54-3 and 54-4 to all BT's and painted red ring around trees above upper blaze.

Note: Both BT's scribed in Section 34 because of extensive beetle tree kill in the area.

Used steel tape and magnetic compass with 19½° east declination. Measured to center of BT's. See map of survey.


This corner set November 16, 1979.

Witnesses: B. English
C. Kelly

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of , 19

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 12-5-79
Rec'd By [Signature]
No. Q-1223-B
corresponding
drawing