


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. B-17

History of original corner establishment:
No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner: At surveyed point set 2 1/2"X30" galvanized pipe with brass cap stamped: Set pipe 10" in ground to rock with mound of stone to cap.

T5S R33 1/2 E
N $\frac{1}{16}$
S3 | S2
1980
OR PLS 1294

Bearing Trees:

A Ponderosa Pine 7" dia. bears S70°W, 100.2 ft., scribed N1/16 S3 BT.
A Ponderosa Pine 7" dia. bears N72°E, 72.7 ft., scribed N1/16 S2 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red. Attached 54-2, 54-4 & 54-9 signs to metal post 6 ft west of corner.

I hereby certify the above corner monument was established as herein described on July 9, 1980.

Witnesses: R. Orton
L. Huntsman
D. Allen



Office of...County Surveyor..... County of...Umatilla
State of...Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of...*December*....., 19...*80*
Howard L. Perry by *Betty Shatto*
(COUNTY OFFICIAL) (DEPUTY)

R-187-B