

USDA-FOREST SERVICE

Index File No. C-13

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

T 5S R. 33½E

R.D. Ukiah

Tract or Survey No. \_\_\_\_\_

Cor. No. 1/4

Merid. Willamette

N.F. Umatilla

County Umatilla

State Oregon

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

None Set

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

Signature

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls 25 ft. east of N-S fence.

Signature

*Howard L. Duff*

Title

Division  
WORKS

Headquarters  
1294

Date  
9/77

7100-52-(13/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At above point set 2 1/2" x 30" galvanized pipe with brass cap stamped:  
Set pipe 16" in ground to rock with mound of stone to cap.

T5S  
R33E | 1/4  
          | R33 1/2 E  
S1 | S3  
1980  
ORPLS 1294

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees:  
A Ponderosa Pine 13" dia. bears N45<sup>0</sup>E, 110.8 ft., scribed 1/4S3BT.  
A Douglas Fir 9" dia. bears S79<sup>0</sup> E, 181.1 ft., scribed 1/4S3BT.

Attached 54-3 and 54-4 signs to both BT's. Attached brass washer stamped LS 1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red. Attached 54-2, 54-4 and 54-9 signs to metal post 6 ft. north of corner.

Work Done By R.C. Orton Title Party Chief Date 7/9/80 State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

**REMARKS**

Witnesses: R. Orton  
              L. Huntsman  
              D. Allen

Index File No.      T.      R.      M.      Tract or Surv. No.      U.S. G.P.O. 1977-725-576/586  
C-13      55      33 1/2 E                Cor. 13