

History of original corner establishment:

Unsurveyed - subdivided section.

T 5S. R. 33 1/2 E.	
NE 1/16	S 11

No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner

Set 2 1/2" x 30" iron pipe 22" in ground with brass cap as shown: from which I scribed Bearing Trees.

A fir 8" diameter bears South 30°18' West 5.85 feet marked NE 1/16 S 11 BT  
 A fir 8" diameter bears South 01°39' West 32.00 feet marked NE 1/16 S 11 BT

I nailed a brass washer marked PLS 933 to the BT blaze of both trees. Set steel fence post 5 feet East of corner. The corner is 1 foot East of North-South fence and is 13 feet South of fence corner of fences running North and East. Used T-2 and steel tape, measuring a horizontal distance to center of Bearing Trees.

REGISTERED  
 PROFESSIONAL  
 AND SURVEYOR  
*David H. Krumben*  
 OREGON  
 JULY 17, 1970  
 DAVID H. KRUMBEIN  
 933

T 5S. R. 33 1/2 E.  
 NE 1/16 S 11  
 1978  
 PLS 933

Office of ..... County Surveyor ..... County of Umatilla .....  
 State of Oregon, I hereby certify that the within instrument was filed in this office for record on the ..... day of .....  
 (COUNTY OFFICIAL) by (DEPUTY)