

History of original corner establishment:

Unsurveyed - subdivided section.

DIAGRAM
T. 5S. R. 33 $\frac{1}{2}$ E.
C $\frac{1}{4}$ S 12

No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner

Set 2 $\frac{1}{2}$ " x 30" iron pipe 22" in ground with brass cap marked as shown: from which I scribed Bearing Trees:

- A fir 10" diameter bears North 78° 15' West 3.95 feet marked C $\frac{1}{4}$ S 12 BT
- A tamarack 12" diameter bears South 08° East 14.55 feet marked C $\frac{1}{4}$ S 12 BT

I nailed a brass washer PLS 933 to the BT blaze of both trees. Set a steel fence post 5 feet East of corner. Used a T-2 and steel tape, measuring a horizontal distance to the center of the Bearing Trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David H. Krumben

OREGON
JULY 17, 1890
DAVID H. KRUMBEIN
933

T 5S R. 33 $\frac{1}{2}$ E.

C $\frac{1}{4}$ S 12

1978

PLS 933

Office of County Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of

..... by
 (COUNTY OFFICIAL) (DEPUTY)