

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Rufus S Moore, U.S. Deputy Surveyor, under GLO Contract No. 451, dated June 12, 1882.


Surveyor General records state:

Set a basalt stone 13 x 8 x 5, 8 ins in the ground for 1/4 sec. cor. marked 1/4 on W face from which:

A pine 20 ins, in dia. bears S 48°E, 37 lks dist marked 1/4 S BT.

A pine 11 ins. in dia. bears S 70°W, 9 lks dist marked 1/4 S BT.

G-5



Description of corner evidence found:

Found a basalt stone 13 x 8 x 5 ins marked 1/4 on West face firmly set in ground.

A ponderosa pine 28" in dia. with open blaze and visible scribe marks brs. S48°E, 24.4' dist (37 lks) per record. No trace of Section 7 bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner:

At position of original corner stone...

Set a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe 22" in ground surrounded with mound of stone only. Set steel fence post 4' North of corner & attached sign 54-9 & 54-2.

New bearing trees established:

A 9 1/2" ponderosa pine brs N47°W, 79.7' scribed 1/4S7 BT.

A 8" ponderosa pine brs N29°E, 92.8' scribed 1/4S8 BT.

A 11 1/2" Western Larch brs. S51°W, 96.4' scribed 1/4S7 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly re-monumented to U.S.F.S. standards by me on October 27, 1993.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

Office of... County Surveyor..... County of... Umatilla.....
State of... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71) Umatilla County Surveyor

Date 8-4-94
Rec'd By KK
No. 94-106-c
3