


10
J-10

History of original corner establishment:

No previous history



Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

I set a 2 1/2" brass cap on a 30" galv. iron pipe and being stamped as shown above, in a large mound of stone and dirt which buried the monument.

New bearing trees:

A pine 6" dia. bears N 35 30 W, 23.33 feet and scribed 1/16 S S 9 BT.
A pine 7" dia. bears N 50 E, 18.25 feet and scribed 1/16 S S 16 BT.

Note: There were no trees available in Section 16 that could be used as a bearing tree, therefore used the second tree also being in Section 9.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
8-21-78

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

I hereby certify the above corner monument was re-established as herein described in August 1978.

Witnesses:

Leonard C. Hansen
Crew Chief

J. P. Huber
Instrument Man

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

J-10