

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


N-7

History of original corner establishment:

Corner originally established by Rufus S. Moore, U.S. Deputy Surveyor, under GLO Contract No. 451, dated June 12, 1882. Surveyor General records state:

Set a post 3 ft. long 3 ins. sq. 24 ins. in ground for 1/4 Sec. Cor. marked 1/4S on W face from which:
A fir 29 ins. in dia. bears N12°W, 18 lks. dist. marked 1/4S BT.

A tamarack 10 ins. in dia. bears S28°E, 10 lks. dist. marked 1/4S BT.
A fir 9" dia. bears S 62°W, 07 lks. dist. marked T 5 S 34 E S 20 BT.
A pine 11" dia. bears S 14°E, 13 1/2 lks. dist. marked T 5 S 34 E S 21 BT.



Description of corner evidence found:

No trace of corner post or bearing trees recovered. This corner was previously searched on 8-28-84 by Dave Dahlstrom, U.S.F.S. staff, and his search record states the area had been burned 80 to 100 years ago. He found no trace of corner or accessories. This corner was searched for a total of 5 hours on 3 separate occasions with a 2 person crew. 2 hours of a professional land surveyor time was spent. A search radius of 150 feet was covered. The corner area burnt on the ground many years ago and has been clearcut. No evidence of the remaining 2 bearing trees in Sec's. 17 & 20.

Description of monument and accessories established to perpetuate the original location of this corner:

At position determined by single proportionate measurement between the recovered Northwest corner and the existing Northeast corner to Section 17, a 2 1/2" brass cap on a 30" galv. iron pipe, and being stamped as shown above, with a 2 1/2" aluminum cap on 2 1/2"x30" aluminum pipe, 26" in ground, surrounded with mound of earth only. Set steel fence post 4' West of corner & attached sign 54-9 & 54-2.

New bearing trees established:
A 16" diam. western larch brs. N3°W, 88.5' mkd 1/4S17 BT.
A 12" diam. western larch brs. N76°E, 52.2' mkd 1/4S17 BT.
A 13" diam. western larch brs. South 31.6' mkd 1/4S20 BT.
A 1 1/2" diam. western larch brs. S33°W, 32.4' mkd 1/4S20 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree. Compass declination 18° East.

I hereby certify that the above corner was properly re-established to U.S.F.S. standards by me on October 27, 1993.

JAMES H. HANLEY

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

renews 12-31-94

Office of County Surveyor County of Umatilla State of Oregon I hereby certify that the within instrument was filed in this office for record on the day of 19... by (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 8-4-94 Rec'd By KK No. 94-106-C 14

U.S. GOVERNMENT PRINTING OFFICE-1983-793-276

94-39-B