

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner originally established by Rufus S Moore, U.S. Deputy Surveyor, under GLO Contract No. 451, dated June 12, 1882.

Surveyor General records state:

Set a post 4 ft. long 4 ins. sq. 24 ins. in ground for Cor. to Secs. 29,30,31 & 32, 300 ft. below 1/4 Sec. Cor. marked T5S S29 on NE, R34ES30 on NW, S31 on SW and S32 on SE faces with 1 notch on S and 5 notches on E edges from which:

- A pine 4 ins. in dia. bears N33°E, 6 lks dist marked T5SR34ES29 BT.
- A pine 5 ins. in dia. bears N49°W, 11 lks dist marked T5SR34ES30 BT.
- A fir 5 ins. in dia. bears S58°E, 34 lks dist marked T5SR34ES32 BT.
- A fir 14 ins. in dia. bears S20°W, 52 lks dist marked T5SR34ES31 BT.

V-5



Description of corner evidence found:

Found rotten remains of original wood post below ground surface from which...

Remains of Section 31 BT, a uprooted 14" diam. fir with visible scribe marks on upper portion of double blaze, brs S20°W, 34.3' (52 lks).

Remains of Section 32 BT, a uprooted and decaying fir 5" diam. with healed blaze brs S58°E, 22.4' (34 lks).

Description of monument and accessories established to perpetuate the original location of this corner

At position of recovered original wood post...

Set a 2½" aluminum cap on 2½"x30" aluminum pipe 26" in ground surrounded with mound of earth & stone. Set steel fence post 4' South of corner & attached sign 54-9 & 54-2.

New bearing trees established:

- A 13" diam. Western larch brs. N1°E, 93.0' mkd T5SR34ES29 BT.
- A 18" diam. white fir brs S52°E, 87.1' mkd T5SR34ES32 BT.
- A 10" diam. lodgepole pine brs S51°W, 43.9' mkd T5SR34ES31 BT.
- A 5½" diam. lodgepole pine brs N78°W, 44.3' mkd T5SR34ES30 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each bearing tree.

Compass declination 18° East.

I hereby certify that the above corner was properly re-monumented to U.S.F.S. standards by me on October 27, 1993.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will - R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

Office of County Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of ; 19 , at o'clock m., (signed)
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
 Date 8-4-94
 Rec'd By KK
 No. 94-106-C
18