



**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying  
**ADDRESS:** P.O. Box 1696  
 357 NE Hwy. 11  
 Pendleton, OR 97801

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*W.R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

*renews 6-30-02  
 7/31/01*

**GRANTEE: PUBLIC**

SEAL/SIGNATURE/DATE

**LEGAL:** TWP: 6N RGE: 32E CORNER CODE: A-11  
**ADDITIONAL IDENTIFIER:** (BLM designation, street or plat names, block, lot, etc.)  
 NORTH ONE-QUARTER CORNER OF SECTION 4

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 868538.86 E: 8629755.76, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

**1. HISTORY:**

Corner originally established by Daniel G. Major under Contract No. 72, dated May 25, 1863. Record states: Set a post for quarter section corner, made mound with trench and pits and drove charred stake.

Line was retracted and corner visited by Edwin Richardson, under Special Instructions dated February 22, 1867.

Corner is referred to on 1916 Survey for Lambdin, File # 2-S-021, Walla Walla County Engineer's Office. Survey calls for "R.Bot" interpreted to mean rock and bottle.

**2. EVIDENCE FOUND:**

Found 9 X 7" set basalt stone, 4" above ground. Stone marked "X" on top.

**3. PERPETUATION INFORMATION:**

Found stone monument at Northwest corner of Section 4 bears North 89° 16'05" West, 2656.36'.

Bearings are based on true north, see accompanying Record of Survey.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.  
 \6N32A11ORN

RECEIVED BY

Umatilla County Surveyor

Date 9-01

Rec'd By [Signature]

No. 01-111-B