

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/06/01

CORNER DESIGNATION: N-15

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U. S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: None, corner falls in farmed CRP field.

MONUMENT MARKING DETAIL:

T6N R32E
S15
1/4-----
S22
2001
PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, 16" below ground surface, stamped as shown in "Monument Marking Detail".
From which:

- A silver deep-1 magnet, buried 20" below ground, bears N 25° E, 38.0 feet.
- A purple deep-1 magnet, buried 20" below ground, bears S 58° E, 36.1 feet.
- A blue deep-1 magnet, buried 20" below ground, bears S 32° W, 36.9 feet.
- A orange deep-1 magnet, buried 20" below ground, bears N 45° W, 37.0 feet.

Buried bearing object tags with along with the deep-1 magnets. Set a steel fence post next to buried monument and attached "witness" sign.

LOCATION AND COMMENTS: Corner is located at a point in a CRP field, in center of a field road.

STATE PLANE COORDINATES, OREGON NORTH, NAD 83(91): *fti*
N: 852937.03
E: 8634463.48

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
\6N32N15

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 9-01
Rec'd By KK
No. 01-139-C