

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/18/01

CORNER DESIGNATION: N-19

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with fences running South and West as best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T6N R32E  
S14  
1/4-----  
S23  
2001  
PLS 1106

MONUMENT SET: Set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe, with top 3" above ground level, N 45° E, 1.0 feet from centerline of fence corner post, cap marked as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 16" in ground bears N 17° E, 52.8 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground level, in fence post, bears S 03° E, 42.3 feet.

A brass washer stamped "PLS 1106, 1.0 feet above ground level, in fence post, bears S 82° W, 33.1 feet.

A orange deep-1 magnet, buried 16" in ground bears N 44° W, 45.6 feet.

Attached bearing object tags to fence posts by brass washers. Buried bearing object tags with deep-1 magnets. Attached "witness" sign to fence corner post Southwest of corner monument.

LOCATION AND COMMENTS: Corner is located at a fence corner with fences running South and West.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91):  $f+L$

N: 853111.98

E: 8639744.00

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
\6N32N19

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-02*

RECEIVED BY  
Umatilla County Surveyor  
Date 9-01  
Rec'd By JK  
No. 01C1374C