

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/18/01

CORNER DESIGNATION: N-23

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone, 15 x 10 x 9, 8 ins. in ground, for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with old fences extending East-West and South as best remaining evidence of the original corner location. Made extensive search for original stone by digging around fence corner post. No stone found.

MONUMENT MARKING DETAIL:

T6N R32E
S13
1/4-----
S24
2001
PLS 1106

MONUMENT SET:

On the North side of fence corner post, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, with top 3" above ground level, marked as shown in "Monument Marking Detail".

From which:

A brass washer stamped "PLS 1106", 1.0 feet above ground level, in wood fence post bears East, 41.5 feet.

A purple deep-1 magnet, buried 16" in the ground, bears S 37° E, 32.6 feet.

A brass washer stamped "PLS 1106", 1.0 feet above ground level, in wood fence post bears West, 29.7 feet.

An orange deep-1 magnet, buried 16" in the ground, bears N 38° W, 32.1 feet.

Attached bearing object signs to fence posts with brass washers. Buried bearing object signs along with deep-1 magnets. Attached "witness" sign to fence corner post near new monument.

LOCATION AND COMMENTS: Corner is at a fence corner with fences running East/West and South.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *54i*

N: 853228.59

E: 8645129.60

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
N32N23

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 9-01
Rec'd By KK
No. 01-139-C