

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/18/01

CORNER DESIGNATION: N-7

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for 1/4 Sec. Cor.

MONUMENT AND ACCESSORIES FOUND: Accepted the intersection of a field line running South and a Fence and field line running East as the best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T6N R32E
S17
1/4-----
S20
2001
PLS 1106

MONUMENT SET:

Set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe with top 3" above ground level, N 45° E, 1.0 feet from centerline of railroad tie fence corner post, monument marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 16" in the ground, bears N 28° E, 31.5 feet.
- A purple deep-1 magnet, buried 16" in the ground, bears S 54° E, 30.1 feet.
- A blue deep-1 magnet, buried 16" in the ground, bears S 62° W, 37.8 feet.
- A orange deep-1 magnet, buried 16" in the ground, bears N 51 1/2° W, 44.5 feet.

Buried bearing object signs along with the deep-1 magnets. Attached "witness" post to railroad tie fence post, near corner monument.

LOCATION AND COMMENTS: Corner is located at a railroad tie fence corner with field line South and fence line running East.

STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *fti*

N: 852646.04

E: 8623806.12

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
16N32N7

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor
Date 9-01
Rec'd By KK
No. 01-139-C