



7-31-01

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

*renews 6-30-02
7/31/01*

SEAL/SIGNATURE/DATE

GRANTEE: PUBLIC

LEGAL: TWP: 6N RGE: 32E **CORNER CODE:**
ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.) 10 MILE CORNER
STATE LINE 10 MILE CORNER

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 855827.71 E: 8642834.07, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Daniel G. Major under Contract No. 72, dated May 25, 1863. Record states: Made excavation, 3 ft. deep; soil stony; deposited 2 charred white thorn stakes; planted post, 8 ft. long and 9 ins. sq., when trimmed; top beveled; ground end charred. Marked on N. face "W", on S. "O", on E. "46° L 1864", on W. "10 M". Built mound, 8 ft. sq. at base & rising to post 3 1/2 ft., composed partly of stone and covered with soil. Dug trench & pits of the usual size. Bearings: To ledge of rock, projecting from ridge top, N 82°09'W., dist. 50 chs. To a similar object, S0°01'30"W., dist. 1 1/3 miles. Point at which horizon is intercepted by ridge, S.48°02'E., dist. 1 mile.

2. EVIDENCE FOUND:

A 3.0 foot diameter mound of native stones between two rock jack of imported stone. NOTE: In this area the old fence jacks, (no wire or wood left), were constructed of imported stone and are spaced about two rods apart: The mound of native stone is about 10 feet from one of the fence jacks constructed of imported stone and stands out. Major's bearing accessories fit "OK" when measured with a compass. Fence jacks indicate the old fence was built through the corner.

3. PERPETUATION INFORMATION:

A center of mound of native stone, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, with cap projecting 6" above the stone mound. Rebuilt stone mound. Cap marked as shown below:

10 MILE
WASH
ORE
2001
OR PLS 1106
WA PLS 17372

continued on back.....

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.
V6N3210mileORN

RECEIVED BY

Umatilla County Surveyor
Date 09-01
Rec'd By KK
No. 01-111-B