



7-31-01

**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying

**ADDRESS:** P.O. Box 1696  
357 NE Hwy. 11  
Pendleton, OR 97801

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02  
7/31/01*

**GRANTEE: PUBLIC**

SEAL/SIGNATURE/DATE

**LEGAL:** TWP: 6N RGE: 32E **CORNER CODE:**  
**ADDITIONAL IDENTIFIER:** (BLM designation, street or plat names, block, lot, etc.) 9.5 MILE  
STATE LINE 9.5 MILE CORNER

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 855782.44 E: 8640247.91, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. **HISTORY:** Corner originally established by Daniel G. Major under Contract No. 72, dated May 25, 1863. Record states: Made excavation, deposited charred cherry stakes. Planted a willow post, 6 ft. long & 5 ins. sq., upper end trimmed; top beveled; ground end charred. Placed two large stones near the post; threw up a small mound (the inclination of the hill being too great for a large one). Dug deep rectangular trench & 3 pits, the lower or E. one being omitted. Post marked on W. face 1/2 M.. Bearings: to ledge of rock on ridge, N 29°26'E., dist., say 50 chs. About 10 chs. S. this ridge descends & makes a gap, then rises in continuation of the ridge to the S.S.E.

2. **EVIDENCE FOUND**

Found two large set stones and rotted post remains to a depth of 8" below ground. There is a fence bearing N 35° W and S 35° E just West of corner. The original bearing call to a ledge of rock (N 29°26' E, approximately 50 chains) bears N 29° E, by compass.

3. **PERPETUATION INFORMATION**

At position of found post remains between the two large set stones, set a 2 1/4" brass cap on a 1" x 30" galvanized iron pipe flush with the ground. Cap marked as shown below:

9.5 MILE  
WASH  
ORE  
2001  
PLS 1106

From which:

A 5/8" x 30" iron rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, in fence line, bears S 35° E, 80.0 feet.

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set flush with ground, in fence line, bears N 34 1/2° W, 89.5 feet.

Set steel fence post with witness sign attached 2.0 feet Westerly of corner in fence line. Compass declination 18° E.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

W6N329.5mileORN

RECEIVED BY

Owasilla County Surveyor

Date 9-01

Rec'd by KF

No. 01-111-B