



7-31-01

**LAND CORNER RECORD**

**GRANTOR/SURVEYOR/PUBLIC OFFICER:** This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

**COMPANY OR AGENCY:** William R. Wells Land Surveying  
**ADDRESS:** P.O. Box 1696  
357 NE Hwy. 11  
Pendleton, OR 97801

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
<i>renews 6-30-02 7/31/01</i>

**GRANTEE: PUBLIC**

<b>LEGAL:</b>	<b>TWP:</b>	<b>6N</b>	<b>RGE:</b>	<b>32E</b>	<b>CORNER CODE:</b>
<b>ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)</b>					<b>9 MILE</b>

STATE LINE 9 MILE CORNER

**COUNTY:** Walla Walla

**OREGON PLANE COORDINATES:** N: 855685.77 E: 8637551.45, (inf ORN 83/91)

**ORDER:**

**CORNER INFORMATION:** Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

**1. HISTORY:**

Corner originally established by Daniel G. Major, under Contract No. 72, dated May 25, 1863. Record states: Made excavation 3 ft. deep. Deposited charred stake & bones. Planted a charred willow post, 8 ft. long & 8 ins. sq.; trimmed at upper end., top beveled; marked on N. face "W", on S. "O", on E. "46° L 1864" and on W. "9 M". Continued on back.....

**2. EVIDENCE FOUND:**

Found 4 1/2' diameter stone mound of large stones. Excavated mound and found post remains and portions of wood post lying horizontally below ground.

**3. PERPETUATION INFORMATION:**

Set 2 1/4" brass cap on 1" x 30" galvanized iron pipe in stone mound at location of post remains. Rebuilt original stone mound. Top of cap protrudes 6" from stone mound. Cap marked as shown below:

9 MILE  
WASH  
ORE  
2001  
PLS 1106

From which:

- A 3" brass disk bench mark in concrete railroad trestle abutment, stamped "USGS K378 1943" bears S 14°29'15" W 89.69'.
- An "XBO" chiseled in large rock approximately 30' North of centerline of old road bears N 14°28'50" W 55.07'.
- The rejected BLM 9 Mile brass cap monument bears N 87°54'45" E 359.81'.
- Set steel fence post 1.0 feet North of monument with witness post sign attached.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

V6N329mileORN

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date 9-01  
 Rec'd By KK  
 No. 01-111-B