



7-31-01

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY: William R. Wells Land Surveying

ADDRESS: P.O. Box 1696
357 NE Hwy. 11
Pendleton, OR 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

*renews 6-30-02
7/31/01*

GRANTEE: PUBLIC

SEAL/SIGNATURE/DATE

LEGAL: TWP: 6N RGE: 33E CORNER CODE: J-9

ADDITIONAL IDENTIFIER: (BLM designation, street or plat names, block, lot, etc.)

CLOSING CORNER ON STATE LINE AT NORTHWEST CORNER OF SECTION 16, OREGON.

COUNTY: Walla Walla

OREGON PLANE COORDINATES: N: 856199.95 E: 8658437.91, (inf ORN 83/91)

ORDER:

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.

1. HISTORY:

Corner originally established by Nicholas O. Walden, under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone, 16 x 8 x 8", 8 ins. in ground for closing corner to fractional Secs. 16 & 17.

2. EVIDENCE FOUND:

Found original 16 x 8 x 8" basalt stone with chiseled grooves lying loose South of rock jack. An ancient fence extends to the South.

3. PERPETUATION INFORMATION:

At position of found stone, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, 6" below ground with a railroad spike alongside as a memorial. Buried original stone South 1.0' from monument 4" below ground. Cap is marked as shown below:

T6N R33E

S17 | S16

CC

2001

PLS 1106

From which:

A brass washer stamped "PLS 1106", 1.0 foot above ground level in a wood fence post bears N 35° E, 106.4 feet.

A 6" diameter well casing, 2.0 feet above ground level bears S 22° E, 141.3 feet, to center line of casing.

A brass washer stamped "PLS 1106", 1.0 above ground level, in wood fence post, bears S 50° W, 58.9 feet.

A irrigation line water spicket, bears N 32° W, 1.3 feet.

Attached bearing object signs to all fence posts with brass washers.

Set steel fence post with witness sign attached South, 7.5 feet in fence line. Compass declination 18° East.

This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

W6N33J9ORN

RECEIVED BY

Umatilla County Surveyor

Date *8-01*

Rec'd By *[Signature]*

No. *01-111-B*