

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/17/01

CORNER DESIGNATION: N-13

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone, 16 x 9 x 7, 8 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22.

Geary Kimbrell, Deputy County Surveyor, recovered this corner under Survey No. 239, dated March, 1906, but does not state what was recovered.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with fences West and South as best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T6N R33E
S16 | S15
S21 | S22
2001
PLS 1106

MONUMENT SET: At a point just North of a 6" diameter metal fence post, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, flush with ground. Monument is stamped as shown in "Monument Marking Detail".

From which:

- A brass washer stamped "PLS 1106", 1 foot above ground level in wood fence post, bears S 03° W, 28.2 feet.
- A 6" diameter metal fence corner post bears S 20° W, 0.8 feet.
- A 6" diameter metal fence corner post brace bears S 82° W, 5.4 feet.
- A brass washer stamped "PLS 1106", 1 foot above ground level in wood fence post, bears N 89° W, 49.1 feet.

Attached bearing object signs to the wood fence posts with brass washers. Set steel fence post North of new corner monument with "witness" sign attached.

LOCATION AND COMMENTS: Corner located at fence corner with fences running West and South.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *fti*
N: 853598.61
E: 8663744.13

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
N6N33N13

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor:
Date 9-01
Rec'd By JK
No. 01-139-C