

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/16/01

CORNER DESIGNATION: N-5

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone, 14 x 10 x 8, 7 ins. in ground, for Cor. to Secs. 17, 18, 19 & 20.

MONUMENT AND ACCESSORIES FOUND: Found 12" x 8" x 6" set stone with an "X" chiseled in the top, at fence intersection with fences East-West.

MONUMENT MARKING DETAIL:

T6N R33E
S18 | S17
S19 | S20
2001
PLS 1106

MONUMENT SET:

At position of found stone set a 2.5 inch aluminum cap on a 2 1/2" x 30" aluminum pipe, with cap 3" above ground level, buried stone on South side of new monument, 2" of stone above ground with "X" visible. Stamped monument as shown in "Monument Marking Detail".

From which:

A brass washer stamped "PLS 1106", 1.0 feet above ground in wood fence post bears East, 31.6 feet.

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", 18" below ground in farmed field bears S 41 1/2° E, 36.4 feet.

A brass washer stamped "PLS 1106", 1' above ground in a fence post bears N 84° W, 63.0 feet.

A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106 WA PLS 17372", 18" below ground in farmed field bears S 34° W 30.1 feet.

Bearing object signs are nailed to posts by brass washers. Buried bearing object tags with the iron rebar accessories. Set steel fence post with "witness" sign South of new monument.

LOCATION AND COMMENTS:

Monument located 1 foot South of East-West fence line.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *fti*

N: 853344.74

E: 8653183.55

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

\6N33N5

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02 RECEIVED BY

Umatilla County Surveyor
Date 9-01
Rec'd By [Signature]
No. 01-139-C