

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/17/01

CORNER DESIGNATION: P-13

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Drove charred stake & raised mound of earth, with pits, etc., as per instructions.

Geary Kimbrell, Deputy County Surveyor, recovered this corner under Survey No. 239, dated March, 1906 but does not state what was recovered.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with fences North-South and West as best remaining evidence of the original corner location. Accepted fence corner location matches Kimbrell's record measurement from the Center 1/4 of Section 21 within a foot.

MONUMENT MARKING DETAIL:

T6N R33E  
1/4  
S21 | S22  
2001  
PLS 1106

MONUMENT SET: On the East side of accepted fence corner, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe with top 1" above ground, stamped as shown in "Monument Marking Detail".

From which:

- The center of a 6" diameter metal H-brace post bears S 3 1/2° W, 16.5 feet.
- The center of a 6" diameter metal H-brace post bears S 4° W, 22.0 feet, with bearing object sign wired to it.
- The center of a 6" diameter metal H-brace post bears West, 0.7 feet.
- The center of a 6" diameter metal H-brace post bears N 05° W, 5.6 feet.
- Set steel fence post North of monument with "witness" sign attached.

All bearings and distances measured 1.0 feet above ground level, to center of metal brace posts.

LOCATION AND COMMENTS: Corner located at fence corner with fences running North-South and West.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, 83(91): *fti*  
N: 850957.42  
E: 8663750.49

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
\\6N33P13

Surveyor's Seal  
REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY  
Umatilla County Surveyor  
Date 9-01  
Rec'd By KK  
No. 01-139-c